Suggested Attachment Installation Service Times

Excavator Attachments			
Attachment	Labor Hour	Remarks	
Bucket	1.5	Pin-On	
Bucket	1	Used with quick coupler	
Coupler	1.5	With factory QC piping installed	
Coupler	8	Without factory QC piping	
Thumb (HT model)	6		
Thumb (PL model)	8		
Grapple	2		
Magnet	1		
Generator	20		

Wheel Loader Attachments		
Attackment		Downston
Attachment	Labor Hour	Remarks
Bucket	2	Pin-On
Bucket	1	Used with quick coupler
Coupler	2	With factory QC piping installed
Coupler	8	Without factory QC piping
Pallet Forks	1	
Full Guarding Kit	24	
Front Window Guard	1	
Air Intake Guard	1	
Boom Cylinder Guards	4	
Front Frame Underguard	3	
Transmission Guard	1	
Rear Frame Underguard	3	
Front Light Guard	1	
Rear Light Guard	0.5	
Axle Seal Guards	2	
Articulation Guard	4	
Front Frame Cover	1	
Valve Stem Covers	2	